

**EVALUATION REPORT OF  
METAL SALES MANUFACTURING CORPORATION  
'26 GA. STILE PANEL'**

**FLORIDA BUILDING CODE 5<sup>TH</sup> EDITION (2014)  
FLORIDA PRODUCT APPROVAL  
FL 11560.8-R2  
ROOFING  
METAL ROOFING**

**Prepared For:  
Metal Sales Manufacturing Corporation  
545 South 3<sup>rd</sup> Street, Suite 200  
Louisville, KY 40202  
Telephone: (502) 855-4300  
Fax: (502) 855-4290**

**Prepared By:  
Bala Sockalingam, Ph.D., P.E.  
Florida Professional Engineer #62240  
1216 N Lansing Ave., Suite C  
Tulsa, OK 74106  
Telephone: (918) 492-5992  
FAX: (866) 366-1543**

**This report consists of  
Evaluation Report (2 Pages including cover)  
Installation Details (2 Pages)**

**Report No. C2009-8  
Date: 3.27.15**



Manufacturer: Metal Sales Manufacturing Corporation

Product Name: Stile

Panel Description: 39.4" wide coverage with (9) 1-3/16" high, 5" wide and 12" long simulated tile profile

Materials: Min. 26 ga., 40 ksi steel. Galvanized coated steel (ASTM A653) or Galvalume coated steel (ASTM A792) or painted steel (ASTM A755).

Deck Description: Min. 15/32" thick plywood for new and existing constructions. Designed and installed as per FBC 2014.

Deck Attachment: 8d x 2.5" long ring shank nails or #8 x 2" long wood screws @ 6" o.c. (Minimum) in the plywood field and edges

Underlayment: Minimum underlayment as per FBC 2014 Section 1507.4.5.1

Slope: 1/2:12 or greater in accordance with FBC 2014 Section 1507.4.2

Design Uplift Pressure: 85.8 psf @ fastener spacing of 24" o.c. (Factor of Safety = 2) 102.7 psf @ fastener spacing of 12" o.c.

Panel Attachment:  
At panel ends ¼"-14 x 1-1/2" long ABMP fasteners @ each valley  
At intermediate ¼"-14 x 1-1/2" long ABMP fasteners @ each other valley


Sidelap Attachment: 1/8" Diameter x 3/16" long steel pop rivets @ 12" o.c.

Test Standards: Roof assembly tested in accordance with TAS 125-03 'Standard Requirements for Metal Roofing Systems'.

Code Compliance: The product described herein has demonstrated compliance with FBC 2014 Section 1507.4

Product Limitations: Design wind loads shall be determined for each project in accordance with FBC 2014 Section 1609 or ASCE 7-10 using allowable stress design. The maximum fastener spacing listed herein shall not be exceeded. This evaluation report is not applicable in High Velocity Hurricane Zone. Fire classification is not within scope of this Evaluation Report. Refer to FBC 2014 Section 1505 and current approved roofing materials directory or ASTM E108/UL790 report from an accredited laboratory for fire ratings of this product.

Supporting Documents: TAS 125-03 Test Reports  
Farabaugh Engineering and Testing Inc  
Project No. T270-06, Reporting Date 11/30/06




TYPICAL PANEL PROFILE

NO.	REVISION DESCRIPTION	BY	DATE

DRAWING TITLE		STIFLE PANEL	
CONSULTANTS	MANUFACTURER	METAL SALES MANUFACTURING CORP.	
BALA SOCKALINGAM, PH.D., P.E.	545 SOUTH 3RD ST., SUITE 200	LOUISVILLE, KY 40202	
1216 N LANSING AVE, SUITE C	PHONE: 918-492-5992	FAX: 866-366-1543	502-855-4300
TULSA, OK 74106			

DRAWN BY:	CHECKED BY:
B.S.	D.S.
PLLOT:	DATE:
	3/25/15

DRAWING NO.	REV.
2009-8A	
PAGE NO.	
1	2




TYPICAL PANEL INSTALLATION X-SECTION

ALLOWABLE UPLIFT PRESSURE

PANEL FASTENERS SPACING ALONG LENGTH	PRESSURE (PSF)
24"	85.8
12"	102.7

**GENERAL NOTES:**

1. ARCHITECTURAL ROOF PANEL HAS BEEN DESIGNED IN ACCORDANCE WITH THE FLORIDA BUILDING CODE (FBC).
2. ROOF PANELS ARE 40 KSI, 26 GA. (t = 0.0178"). STEEL EFFECTIVE COVERING WIDTH OF PANEL = 39.4".
3. THE ROOF PANELS SHALL BE INSTALLED OVER SHEATHING & STRUCTURE AS SPECIFIED ON THESE DRAWINGS.
4. REQUIRED DESIGN WIND LOADS SHALL BE DETERMINED FOR EACH PROJECT. THIS PANEL SYSTEM MAY NOT BE INSTALLED WHEN THE REQUIRED DESIGN WIND LOADS ARE GREATER THAN THE ALLOWABLE WIND LOADS SPECIFIED ON THIS DRAWING.
5. ALL FASTENERS MUST BE IN ACCORDANCE WITH THESE DRAWINGS & THE FLORIDA BUILDING CODE. IF A DIFFERENCE OCCURS BETWEEN THE MINIMUM REQUIREMENTS OF THESE DRAWINGS & THE CODE, THE CODE SHALL CONTROL.
6. RAFTERS/JOISTS/TRUSSES MUST BE DESIGNED TO WITHSTAND WIND LOADS AS REQUIRED FOR EACH APPLICATION AND ARE THE RESPONSIBILITY OF OTHERS.



TYPICAL FASTENER SPACING

DRAWN BY: B.S.	CHECKED BY: D.S.
PLOT:	DATE: 3/25/15
DATE	
BY	
REVISION DESCRIPTION	
NO.	

**STILE PANEL**

CONSULTANTS  
**BALA SOCKALINGAM, PH.D., P.E.**

MANUFACTURER  
**METAL SALES MANUFACTURING CORP.**

1216 N LANSING AVE, SUITE C  
TULSA, OK 74106  
PHONE: 918-492-5992 FAX: 866-366-1543

545 SOUTH 3RD ST., SUITE 200  
LOUISVILLE, KY 40202  
502-855-4300

DRAWING NO. <b>2009-8B</b>	REV.
PAGE NO. <b>2</b>	OF <b>2</b>